

ADDENDUM 1: Monte Cristo Water Main Replacement

MONTECITO WATER DISTRICT

January 3, 2023

ADDENDUM NO. 1

TO REQUEST FOR PROPOSALS
Monte Cristo Water Main Replacement
Project # P77

DATED December 2022

Notice is hereby given to bidders that this addendum is issued to make changes to the contract documents, construction drawings, and construction specifications. The following changes shall be made to the contract documents, construction drawings, and construction specifications by the Contractor.

ADDENDUM 1: Q&A

- Q1. The bid item list states there are 12ea. 1" service connections. However, the plans show only 7ea. 1" service connections. The plans show 5ea. ¾" service connections. Please confirm if the ¾" services are to be bid as 1".
- A1. Yes, ¾" service meters are to be installed with a 1" service lateral and bushed down to ¾" at the meter as described on detail 3 sheet A-424-5 of the project drawings.
- Q2. Please confirm the northern limits of abandonment for the existing DIP on Channel Drive.
- A1. The contractor will be expected to cut and cap the existing line with a 6" MJ endcap just north of the existing hydrant being replaced at STA 10+00.

APPROVED:



David Wong, E.I.T.
Engineering Assistant